

Bill of Quantities of Furnishing and allied works for Central Bank of India Branch at PANIPAT BSNL Under RO KARNAL

A) Total Furniture and allied works				
Sr No.	Item	Unit	Qty.	Rate
		Sq.ft		
1a	FALSE CEILING – (GYPBOARD) IN BRANCH HALL AND ENT. LOBBY			
	Providing & Fixing false ceiling at 9'-0" ht. which includes G.I. perimeter channels of size 0.55mm thick (having one flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling screw fixed to brick wall/partition with the help of nylon sleeves and screws, at 610mm centers. Then suspending G.I. intermediate channels of size 45mm (0.9mm thick with two flanges of 15mm each) from the suffix at 1220mm centers with ceiling angel of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. Cleat and steel expansion fastners ceiling section of 0.55mm thick having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediated channel at 457mm centers. Note: <u>Only reflected ceiling plan length and width from bottom shall be measured and verical patta will not be measured.</u>	Sq.ft	960	
1b	ARMSTRONG TILES CEILING			
	Providing and fixing of false ceilings at all heights of 600 mm X 600 mm X 16 mm ARMSTRONG/DEXUNE Mineral Fibre ceiling tiles of type Prima Dune Premier-Beveled Tegular Edge RH-99 laid on Armstrong 15mm exposed grid system. The framework compromise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjuster and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 X 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm X 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200mm cross tees.	sq.ft	480	
2	PARTITIONS			
	Providing and fixing partition in position as per design with 2"X1½ "sal wood finished section frame work @ 2'-0" c/c both ways screwed to the floor and ceiling with M.S. Cleats and All wood frame work to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti termite properties.The measurement will be taken up to the false ceiling visible height in case of full height partition. The frame work will be claded with 6mm thick plywood both sides and to be finished with approved 1.0mm laminate (century laminates- Bavaria beach or similar shade for other approved brands as approved by Bank's Officials) with horizontal grooves 1/8" x 1/8" as per design with approved band adhesive. Extra frame work to be fixed for fixing glass. Teak wood lapping 3"X3/4" all complete duly natural polished and Melamine finish to be provided on all exposed sides. In the glazed partition 12mm thick clear float glass of approved make with Etching/sand blasting/granular blasting & Central bank logo to be provided duly fixed with teak wood lapping 2"X1" all complete duly natural polished and Melamine finish. In case of Full ht. Partly glazed/full glazed partition some portion to be raised as per drawing.			
	The work should be completed as per specification, design & approval of the Bank's official. For the cash cabin door 32mm solid core BWP flush door with a frame work of approved shade, size 3"X 2.5" with necessary hold fast fixed to the wall/partition. Finished with 1.0mm laminate and lapping in all sides and 1.5"X1.5" teak wood molding to be provided along the periphery of the door frame. Supply and fixing of complete door accessory/hardware as door closure, brass hinges, Cylindrical / Night latch, locks and S.S. handle.For manager cabin door, 12mm thick etched glass and Central bank logo frosted design with necessary and blasting/granular blasting to be provided and edge should be machine beveled polished complete with a decorative handle of 600mm of approved brand, floor spring, Locks, door stopper, etc., all complete.			
a	Low height partitions with 12 mm thick glass above 3'-0" ht. upto 4'-6" ht. as per design / drawing.	Sq.ft	100	
d	BM CUBICLE(partly glazed upto 7' ht only) & other full ht UPS and Server Store Room partition, & daftri side full ht. partition rates upto 12'-0" High.	Sq.ft	500	
e	Wick. Gate	R.ft	3.25	
f	Solid Flush Door 5NOS. (nos.7'x3'+nos. 2'6"x7') <u>with door closer, lock set etc including all hardwares complete. Size may vary as per site measurements.</u>	Sq.ft	100	

g	12mm thick Toughened Glass Full Height Partition (2nos 3'x7', 0 nos. 3'x7' at main gate) PLUS as per site full ht glazing complete with Stainless Steel fittings, 16" SS door handle, Locks, studs, frames, etc. complete, with Approved make (Dorma / Ozone/GEZE floor spring with Fittings & Handles etc). <u>Quoted Rate should be including all hardware as required on site for Complete doors and glazing in all respect.</u>	Sq.ft	110	
3				
	Pillar : P/F wall paneling on soft wood frame 1" x 2" placed @ 1'-6" c/c horizontally & vertically, finished with 6mm thick plywood by making horizontal grooves of size 1/8"x1/8" @ 18" c/c, 1.00 mm thick laminate, 4'-0" high as per design, the paneling shall be closed with 1.5" x 3/4" teak wood beading. Item might be changed with HDMR hence rates should be considered.	Sq.ft	500	
4	BANKING COUNTERS /OFFICER TABLES			
a	Table set Size: - 6'0"x2'6"x2'6" with 8mm glass table top ,WITH Side Table Size: - 3'0"x1'6"x2'3": Providing & Fixing BM table & side table made out of 18mm thick Commercial ply frame work & necessary 2" X 2" & 2" X 1 1/2" C.P.T.Wood supports & beeding patti as required / shown in the detail drawing. The table shall have 1'-6" wide drawer unit with two drawers and one shutter below the drawers at the right side of the table along with two drawers in side table & one drawer for key board at the corner of the table & side table. The front apron shall be made in 12mm thk Commercial ply covered with additional 4" X 1/2" thk Commercial ply finish with 1.00mm thick approved shade / make/laminate as shown in detail drawing or as per Banks Standard Design.All the exposed surfaces of the table & side table shall be finish in 1.00mm thick approved color laminate from out side & 1.5mm thk approved color laminate for approved color laminate from out side & 1.5mm thk approved color laminate for TOP finish with French polish from inside of matching of the laminate shades including approved Brush Finish Stainless Steel Handles, Brass Ball Catches, Brass Locks, Foot Rest made out of 12mm thk Commercial ply tapered box finish with Rubber Matting, Brass Powder Coated Wire Manager, Twin Telescopic Drawer Fittings, CPU metal stand with casters, necessary teak wood round 2" Moulding etc. complete as per instructions of the Architect. Rate should be including all hardware as required on site for Completion in all respect.	Nos.	1	
b	Table Size: - 5'0"x2'6"Wx2'6"ht WITH Side Table Size: - 3'0"x1'6"x2'3":Do as above Table specs except in size etc complete as per instructions of the Architect,wherever required.	Nos.	5	
b1	Table Size: - 5'0"x2'6"Wx2'6"ht ::Do as above Table specs except in size etc complete as per instructions of the Architect,wherever required.	Nos.	3	
c	Providing and fixing side rack, 2'-3" ht. as per design. These racks shall have two drawers with storage below and be made of 19mm thick plyboard; 1mm thick laminate with rubber -wood gola of size 1 1/2" x 3/4" polish, painting inside only, side golas, handles, catchers, hinges etc.	Rft	0	
5	STORAGE UNITS			
a	Low Height Storage Unit (Back Side Runner) : Providing, Constructing and Fixing Storage should be made out of 19 mm thk Plyboard box type in nature. 1.0 mm thk approved laminate to be stuck to all exposed surfaces, inside painting, complete finished with golas/margins, 4" S.S.handles, brass hinges, locks and magnetic catchers, etc. Storage should have side hung shutters. The unit to have 3" covered skirting with approved laminate. The overall size of the unit shall be 2'-6" in ht and 18"/15" deep as per design. The unit shall have intermediate shelf.	Sq.ft	100	
B	Full Height Storage Unit (Back Side Runner) : upto 8' ht Providing, Constructing and Fixing Storage should be made out of 19 mm thk Plyboard box type in nature. 1.0 mm thk approved laminate to be stuck to all exposed surfaces, inside painting, complete finished with golas/margins, 4" S.S.handles, brass hinges, locks and magnetic catchers, etc. Storage should have side hung shutters. The unit to have 3" covered skirting with approved laminate. The overall size of the unit shall be in ht and 18"/15" deep as per design. The unit shall have intermediate shelf.	Sq.ft	340	
C	ELECICAL PANEL CUPBOARD 4'x8': Same as above item 5.b except to provide a glass cutout of 1'x1' to make the meter visible.	Sq.ft	36	
6	CASH COUNTERS:			
	Providing & Fixing Cash – counters 2'-9" wide, with two levels i.e. 2'-6" & 4'-0" ht. The lower portions top & all other exposed surface shall have 1mm thick laminate and golas/margins. The lower portion on cashier side there will be provision of 3 nos. drawers with sliding channels of Ebco. for cash, stationery, key board, etc. The upper portion, i.e. customers' level shall have granite top 12" wide as well as 12mm th. glass 9" wide as per detailed drgs. Inside of cash counters shall be painted with synthetic enamel paint as per color scheme, teak wood beadings / gola etc. complete finished with S.S. handles, brass hinges, locks and magnetic catchers, etc	Rft	5	
7	NOTICE / SOFT BOARDS			

a	Providing & fixing soft boards of size 3'-6"x 2'-0" (covered with openable glass shutters) on 10mm th. ply board 12mm th. soft board finished with cotton fabric , 1"x2" teak wood beading.	Nos.	1	
8	SERVER COUNTER:			
	Providing & fixing server room: Counter 2'-6" high with key board, storage cabinet below, drawers etc. other hardware, such as S.S. handles, brass hinges, locks and magnetic catchers etc. shall be shall be provided as per requirement, finished with 1.00 mm thick laminate, inside painting etc. complete in all respects as per drgs.	Rft	4.5	
9	Cheque drop box 1'x2', laminated as above with lock arrangement.	job	1	
10	Writing desk 4'x1'-3', fixed at 3'-6" High. laminated as above with side hung shutters and intermediate shelf.	job	1	
	A.Total Furniture and allied works (Rs.)			

B)	ELECTRICAL, AC & NETWORKING WORKS:			
	ELECTRICAL items:	Unit	Qty.	

Amount
0.00
0.00
0.00
0.00
0.00
0.00

0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00

0.00
0.00
0.00
0.00
0.00

