

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

ALL ITEMS IS TO BE MADE AT SITE AND WOODEN RAW MATERIALS SHOULD BE GOT CHECKED BEFORE PASTING LAMINATES. NO FURNITURE ITEMS SHOULD BE MADE IN FACTORY / WORKSHOP

S.No.	Item/Description	Qty.	Unit	Rate	Amount
1	Dismantling and removal of existing furniture counter, modular workstations, tables, Storage units, partitions , doors etc. and its disposal upto any lead and level. (Minimum area of full / low height partitions to be dismantled - 500 sqft, minimum total workstations to be removed = 20)	1	Lumpsum		
2	<p>Partition works (only with HDHMR/EDHMR boards–Century/ Greenply/Archidply). The thickness of plyboards/plywoods mentioned below is for boards without laminates</p> <p>(Specification for item No. 2A).</p> <p>Measurement of height shall be taken from finished floor level up to the level of false ceiling in case of full height partition. In case of low height the measurement of height shall be taken from FFL upto the beading top. In case of varying heights on either side of partition, average heights shall be considered. The rate to include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc, making provision for laying conduct as per drawings and directions of site Eng. / Architect. It also includes teak wood properly polished / laminated top beading on all sides as per the requirement of specified size as per the directions of Engineer. The work also includes provision of door as per requirements along with all lock (Godrej) Handle, Hinges (5.5) stoppers, door closures etc. as per bank's architect instructions. The rate also includes at no extra cost providing extra framework support above false ceiling upto RCC slab at every 4ft or less distance so as to make entire full height solid/glazed/semi-glazed partition rigid and firm.</p> <p>2 A - Providing and fixing full height / low height solid partition / glazed partition from floor level up to the level of false ceiling or upto required height with frame work of aluminium with sections 1.75" x 1.75" at spacing not exceeding 600mm centre to centre in vertical direction. (Vertical member to be in one piece) and horizontal direction with 7 mm or more thick boards to be fixed on both sides, including grooves as per instructions and 1.0 mm thk laminate to be fixed (both sides) on top complete with polishing / painting the beading surafce with spirit polish as per design and to the satisfaction of Architect/Employer. For glazed partition – item also includes 10mm Glass above 900 mm to 1350/1800/2100/2400/2700 mm fixed in 75x15 mm beading as per specifications fixed around opening finished with melamine matt polishing/laminate. Rest of specifications same as MAIN specifications of Partitions. Complete to the</p>	1100	SQFT		

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

	satisfactions of Architect/ Bank.				
3	Providing and fixing wall panelling as per design & pattern with atleast 1.5"x 1" aluminum frame at 2'-0" c/c in both directions with 7mm or more thick HDHMR boards on top and finished with 1.0 mm laminate. The panelling to be screwed to the frame work; as per design and details. The wood surfaces to be finished in melamine polish complete. Top of the paneling edges / is to be provided with laminate or teak wood decorative beading of 35mm x 15 mm finished with polish/painting as directed.	500	SQFT		
4	Providing and fixing – Doors -Providing and fixing solid flushed door / glazed door having specification as solid / glazed partition in item no. 2 (a) min 35mm thick finished on both sides with 1.0mm thick laminate of approved shade as indicated in drawing. Shutter to be lipped on all sides with 12mm thick teak wood beading. Applicable hardwares to be considered for following doors according to requirement as per detailed drawings including below mentioned hardware-Door closer,SS Ball bearing Hinges ,SS foot operated Door stopper,SS Mortise Latch Lock / concealed dead lock,SS Mortise Handle. All material is of approved brand. approx size of door 750 x2100.	4	Nos.		
5	Opening, Removing, Shifting, Refixing, Alignment etc. of Existing Modular Partitions, tables, counters etc. including minor repairs wherever required as per the directions of Engineer-In-Charge complete in all respect (approx. area = 300 to 400 sqft approx.)	1	Lumpsum		
6	FILE STORAGE CABINETS(all inside structure only with HDHMR/EDHMR boards– Century/Greenply/Archidply; for shutters 19mm plyboard with Greenply (ecotec) / Century (sainik) / Archidply (classic)) :Providing and fixing the 1'-6" deep storage units. The storage units shall have shutters made in 17mm or more thick boards and finished in laminate of approved shade including top. Laminate to be provided in 1 mm thickness (exterior) and 0.8 mm thick (interior). The storage units shall have intermediate shelves in 17mm or more thick HDHMR/EDHMR boards with matching wood lipping. Backply to be in thickness 7mm or more thick HDHMR/EDHMR boards. The storage shall have matching wood edge molding as per the detail drawings. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc of approved make.	300	SQFT		
7	FURNITURE - (specifications for items from 7A to 7C) [only with HDHMR/EDHMR boards– Century/Greenply/Archidply} . All Tables / counters/ work stations to have 17mm or more thick boards top and sides to be with 17 mm or more boards and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area, drawer units is to be made from 17 mm or more one side boards with 1.0 mm laminate finish. The drawers to run on telescopic drawer				

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

	<p>channels. Drawer units to have two smaller and one bigger drawers and locking arrangement (Godrej, ozone, dorma). Foot-rest 75x50mm 2nd class cedarwood member to be fixed for each table the rate to include all hardware such as drawer channels, SS handles etc. The inside of the table to be provided with 0.8 mm thick laminate (White cream shade). The item also includes a tray for key board running on telescopic channel (ozone/hettich), finished with laminate on top and rounded front size 560x450 readymade CPU trolley with castors etc. complete. (EBCO make).</p> <p>All Tables / counters/ work stations to have 17mm or more thick boards top and sides to be with 17 mm or more boards and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area, drawer units is to be made from 17 mm or more thick boards for the front and rear, 11 mm or more boards for sides and 7mm or more thick boards for the bottom with 1.0 mm laminate finish. The drawers to run on telescopic drawer channels. Drawer units (approx. size-400x450x680) to have two smaller and one bigger drawers (or storage below one drawer as required by Bank) and locking arrangement (Godrej, ozone, dorma, hettich). Foot-rest 75x50mm 2nd class cedarwood member (polished) to be fixed for each table the rate to include all hardware such as drawer channels, SS handles etc. Front modesty with 17 mm or more thick boards and 1 mm laminate as per designed in straight / curved shape. The inside of the table to be provided with 0.8 mm thick laminate (White cream shade). The item also includes a tray for key board running on telescopic channel, finished with laminate on top and rounded front size 560x450 readymade CPU trolley with castors etc. complete. (EBCO make)</p> <p>(above specifications are for items from 7A to 7C)</p> <p>Item 7A - Providing and fixing DGM / AGM Table as per main specification but finished in 1 mm laminate in two or more colours. The table size to be 1500x750x750 mm. The item also includes Side cupboard with Laminate finish as per the specifications / design by Bank with size 900x450x750.</p>	6	Nos.		
7B	<p>7B - Providing & placing in position BANKING COUNTER TABLE with 2 FT wide x 2.5 FT high made of 17 mm or more thick boards working top front in straight / curved shape and 1.0 mm laminate finish on exposed surfaces with 0.8 mm thick laminate inside/all the surfaces instead of painting the surfaces / area. Counter items also includes Front modesty with 17 mm or more thick boards and 1 mm laminate as per designed in curved shape as shown in drg. Drawer units to be as specified in MAIN specifications. BUT with divisions for currency as per BANK's instructions, The drawer units to have LOCKING system (Godrej / ozone). One footrest per occupant, key board tray 560x450 laminate finish, CPU stand All as per MAIN Specifications for tables, counter is finished with 0.8 mm thick laminate (white/cream) inside the counters</p>	200	RFT.		

PRICE BID (TO BE FILLED ONLY IN ONLINE MODE)

	<p>& drawer units etc, complete to the satisfaction of Architect/Bank.</p> <p>Mode of Measurement: 1 RFT of Table = 1 FT Length x 2 FT Wide x 2.5 FT Height</p>				
7C	<p>7C- CONFERENCE / MEETING TABLE: Table top shall be in 25mm thick HDHMR Board with 2mm thick PVC edge banding. Table understructure shall be made with HDHMR boards with 2mm thick PVC edge banding. Gable ends shall be 25 mm thick and modesty panels shall be in 18mm thick panels. The table shall have provision for electrical, data etc. points and any other things required for completion of conference table complete in all respect upto the satisfaction of Engineer-In-Charge</p> <p>Mode of Measurement: Plan area from the top.</p>	100	SQFT		
8	Buyback of existing modular workstations, partitions, tables, etc. including transportations cost, complete in all respect.	-1	Lumpsum		
	GRAND TOTAL =				
Total in words -					

Above rates and amounts are excluding GST and GST as applicable shall be charged extra.