

CENTRAL BANK OF INDIA, MARKETYARD OFFICE INTERIOR WORK								
CORRIGENDUM-1 DATE : 20-06-2026								
S. NO.	FLOOR	ITEM NO.	SPECIFICATION AS IN TENDER	MODIFIED SPECIFICATION	QTY	UNITS	RATE	AMOUNT
1	GR. FLR	39	TACTILE -Providing and Fixing SS Tactile Size of 300mmX600mm Installation With Adhesive backed etc complete as directed. Note Coloured, pattern etc will be approved by Architect Bank by considering basic rate for the tiles. (Main Banking area)	A Self Adhesive SS 304 grade Chrome Tactile Strips and dots (Guiding and Warning Tiles) to the cash counter and ATM from the entry point of the ramp or as directed by the Bank.				
				a.SS Tactile strip - 280mm x 35mm x 4mm straight line surretion on top with 3M adhesive VHB tape for fixing - (base rate Rs. 250/- per no)	70	Nos		
				b. SS solid stud - 35mm dia and 5 mm thick with concentric circles on top with 3M adhesive - (base rate Rs. 40/- per no.)	30	Nos		
2	BASEMENT	2	FIRE RESISTANT PARTITION -Partition of Solid fire resistant partition with ventilation SOLID PARTITION -Solid partitions (Below ceiling) - Providing and fixing Full ht partition.Both side laminate , Partitions as per specifications & drawings with instructions complete in all respects. Main frame -2"x2" Aluminum section of 16 Gauge verticals at minimum 2'-0" Centre spacing approx. and 2" X 1" size Aluminum sections horizontal at 2'-0" Centre spacing approx. extra frame below slab soffit for conduit to run above,& Skin:- Solid fire resistant 12mm thk ply screwed to frame work on both sides with joints as shown or directed. Finishing : Both side finished in Calsium silicate with paint as shown in drawing or as directed by Architect	FIRE RESISTANT PARTITION -with ventilation louvers- Providing and fixing Full ht partition having internal side finish with calcium silicate &outer side finished with 12mm ply and laminate, Partitions as per specifications & drawings & having 2 hrs fire resistance .with instructions complete in all respects. Main frame -2"x2" Aluminum section of 16 Gauge verticals at minimum 2'-0" Centre spacing approx. and 2" X 1" size Aluminum sections horizontal at 2'-0" Centre spacing approx. extra frame below slab soffit for conduit to run above,& Skin:- 12mm thk calcium silicate sheet screwed to frame work from inside with joints as shown or directed,12mm solid fire resistant ply from outside. Finishing : Plastic paint on Calsium silicate sheet &laminte on ply as per drawing or as directed by Architect	32	SQM		
3	BASEMENT	7	FLUSH DOOR -Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade as per detailed drawings approved face Laminate 1 mm thick on both faces or as directed & 300 x300m glass vision panel with all necessary mouldings and lipping with polish, chromium plated fixtures and fastenings, with lock, handles on both sides, and finishing with French Polish etc. complete.	FLUSH DOOR -Providing and fixing solid core flush door shutter in single/double leaf 32 mm thick with 2 hour resistance . Approved face Laminate 1 mm thick on both faces or as directed & 300 x300m glass vision panel with all necessary mouldings and lipping with French Polish, chromium plated fixtures and fastenings, with lock, handles on both sides, and finishing with etc. complete.	1.2	KGS		
4	MISCELLANEOUS	6	Deck slab for UPS floor	Providing and fixing checkered plate floor for UPS-battery with 75x75x5mm angle at peripheral,50x50x5mm angle at 1' C/C & 3mm checkered plate above. Also antistatic mat (2mm thick) on checkered plate ,as per design & directed by Architect.	1000	KGS		
		7	Deck slab concrete for UPS floor					
		8	Deck slab Steel for UPS floor					
5	FIRST FLOOR	12	6" TIER IN RAISED PLATFORM -Providing and fixing 6" height raised flooring Platform in MS frame of 2" x 1'6" square tube of 14 Gauge thick frame of 600 mm x 600mm c/c with 18 mm plywood on the top finished in 6mm thick Nylon carpet including with necessary hardware such as corner patti for steps etc as per approved design. (For Coference Hall) Basic Rate of Nylon Carpet - 160 / Sqft	6" TIER IN RAISED PLATFORM -Providing and fixing 6" height raised flooring Platform in MS frame of 2" x 1.5" square tube of 14 Gauge thick frame of 600 mm x 600mm c/c with 18 mm+18mm thk plywood on the top finished in 6mm thick Nylon carpet including with necessary hardware such as corner patti for steps etc as per approved design. (For Coference Hall) Basic Rate of Nylon Carpet - 160 / Sqft. The rate shall include the hardware required for bolting the auditorium chairs(124 nos) to the stepped floor such as Zinc T-nuts, bolts, construction adhesives, etc.	55.00	SQM		

6	FIRST FLOOR	13	12" TIER IN RAISED PLATFORM -Providing and fixing 12 "height raised flooring Platform in MS frame of 2" x 1'6" square tube of 14 Gauge thick frame of 600 mm x 600mm c/c with 18 mm plywood on the top finished in 6mm thick Nylon carpet including with necessary hardware such as corner patti for steps etc as per approved design. (For Coferance Hall) Basic Rate of Nylon Carpet - 160 / Sqft	12" TIER IN RAISED PLATFORM -Providing and fixing 12 "height raised flooring Platform in MS frame of 2" x 1.5" square tube of 14 Gauge thick frame of 600 mm x 600mm c/c with 18 mm +18mm plywood on the top finished in 6mm thick Nylon carpet including with necessary hardware such as corner patti for steps etc as per approved design. (For Coferance Hall) Basic Rate of Nylon Carpet - 160 / Sqft. The rate shall include the hardware required for bolting the auditorium chairs(124 nos) to the stepped floor such as Zinc T-nuts, bolts, construction adhesives, etc.	38	SQM		
7	SECOND FLOOR	7	6" TIER IN RAISED PLATFORM -Providing and fixing 6" height raised flooring Platform in MS frame of 2" x 1'6" square tube of 14 Gauge thick frame of 600 mm x 600mm c/c with 18 mm plywood on the top finished in 6mm thick Nylon carpet including with necessary hardware such as corner patti for steps etc as per approved design. (For Coferance Hall) Basic Rate of Nylon Carpet - 160 / Sqft	6" TIER IN RAISED PLATFORM -Providing and fixing 6" height raised flooring Platform in MS frame of 2" x 1.5" square tube of 14 Gauge thick frame of 600 mm x 600mm c/c with 18 mm+18mm thk plywood on the top finished in 6mm thick Nylon carpet including with necessary hardware such as corner patti for steps etc as per approved design. (For Coferance Hall) Basic Rate of Nylon Carpet - 160 / Sqft. The rate shall include the hardware required for bolting the auditorium chairs(124 nos) to the stepped floor such as Zinc T-nuts, bolts, construction adhesives, etc.	55.00	SQM		
8	SECOND FLOOR	8	12" TIER IN RAISED PLATFORM -Providing and fixing 12 "height raised flooring Platform in MS frame of 2" x 1'6" square tube of 14 Gauge thick frame of 600 mm x 600mm c/c with 18 mm plywood on the top finished in 6mm thick Nylon carpet including with necessary hardware such as corner patti for steps etc as per approved design. (For Coferance Hall) Basic Rate of Nylon Carpet - 160 / Sqft	12" TIER IN RAISED PLATFORM -Providing and fixing 12 "height raised flooring Platform in MS frame of 2" x 1.5" square tube of 14 Gauge thick frame of 600 mm x 600mm c/c with 18 mm +18mm plywood on the top finished in 6mm thick Nylon carpet including with necessary hardware such as corner patti for steps etc as per approved design. (For Coferance Hall) Basic Rate of Nylon Carpet - 160 / Sqft. The rate shall include the hardware required for bolting the auditorium chairs(124 nos) to the stepped floor such as Zinc T-nuts, bolts, construction adhesives, etc.	38	SQM		

Electrical BOQ - Additional Item

Quotation of the following items shall be added in the Electrical BOQ

S. NO.	FLOOR	ITEM NO.	SPECIFICATION AS IN TENDER	MODIFIED SPECIFICATION	QTY	UNITS	RATE	AMOUNT
1				Supply and Installation of 6-32A SP MCB to be installaed in existing box	80	NOS		
2				Supply and Installation of 16-40A TP MCB to be installaed in existing box	12	NOS		

Notes :-

- 1) Basic Rate of laminate to be considered as Rs.65/ sq.ft
 - 2) Floor protection sheet for entire floor including, flrs, toilets, passages, staircase etc shall be compulsorily provided by contractor without extra cost
 - 3) Tender Fees & EMD can be submitted in the for of DD or online mode as under:-
 - (a) In the form of DD - In the name of CENTRAL BANK OF INDIA payable at PUNE
 - (b) Online mode - Through RTGS/ NEFT
- Name of Account - CENTRAL BANK OF INDIA ZONAL OFFICE PUNE
A/C NO. - 1196396023
IFSC - CBIN0280658
BRANCH - POONA CAMP BRANCH